### **NOTICE**

No.EE/Elect.Div./MB/ / 2019 Date:-

#### Mumbai Housing & Area Development Board, A Unit of MHADA.

Subject:-To issue the quotations for Sewerage Treatment Plant (STP) 300 KLD capacity and Organic Waste Composter (OWC) 845 Kg/Day for Mahavir Nagar project of 219 Transit & 172 MIG type Tenements, on turnkey lumpsum basis on land bearing C.T.S No. 128 A-1/2 (Pt) at Mahavir Nagar, Kandivali (West), Mumbai. (Electrical & Mechanical work only)

The sealed quotation are invited by the Executive Engineer, Electrical Division, Mumbai Housing and Area Development Board, Room No.368, seconds floor, Gruhnirman Bhavan, Kalanagar, Bandra (East), from the experienced Sewerage Treatment Plant contractor having vast experienced in the field for obtaining the rates of items given below-----

It	Description of Item	Rate	Unit	Amount
N		(In	(One	
0		Rs.)	Job)	
1.	Design, Supplying, Erection, Testing, Commissioning of 300 KLD Sewerage			
	Treatment Plant with all necessary approval N.O.C. completion certificate etc Plant			
	includes Bar Screen Chamber, sewerage transfer pump, Anoxic tank recirculation			
	pump, Air blower, Air grid with diffuser membrane mediafor Bioreactor (MBBR), tube			
	media, sludge pump, PAC dosing pump, filter feed pump, Pressure sand filter, Activated			
	carbon filter ,centrifugal machine,ozonator, Interconnecting piping &			
	fittings, Instruments , control panel, cabling , Electrical fittings complete. Including 3			
	years free Operation & Maintenance (including labour and material)			
2	Design, Supplying, Erection, Testing, Commissioning of 750 Kg/Day Organic Waste			
	Composter (OWC) with all necessary approval N.O.C. completion certificate etc Plant			
	includes Shredder assembly, Composter drum and MS-FRP supporting structure.			
	MOC- PVC made compost collection trays, powder coated cabinets with provision for			
	electricity meter. Instruments, Control Panel, Cabling, Electrical fittings complete.			
	Including 3 years free Operation & Maintenance (including labour and material)			

In case any query please contact—

Mr.N R Deshmukh, Deputy Engineer (Elect)-022-66405265.

Mr. Amit Shinde ,Junior Engineer (Elect)-022-66405219.

#### **Terms & Conditions:**

- 1. The quotation in sealed cover shall be received in this office as mentioned above within 8 days.
- 2. The quotations shall quote the rates in ink both figure and works.
- 3. The rates should be quoted exclusive of GST & GST rates should be mentioned separately.
- 4. The name of the work for which the quotation is submitted shall be stated clearly on the envelope containing the quotation.
- 5. The quotations without signature of agency may not be considered.
- 6. The above quotation are invited to ascertain the rate only.
- 7. The rates of both STP & OWC should be quoted separately.

Executive Engineer
Housing Electrical Engineer
M.H. & A. D.Board

# मुंबई गृहनिर्माण भवन व क्षेत्रविकास मंडळ

दुरध्वनीक्र :०२२-६६४०५२२० ई-मेल :<u>agbhasharkar@mhada.gov.in</u>

जा.क्र.का.अ./विद्युत/मु.मं./कोटेशन / / २०१९

कार्यकारी अभियंता विद्युत विभाग , मू. गृ .व क्षे. वि. मंडळ रूम क्र . ३६८ , दुसरा मजला , गृहनिर्माण भवन, कलानगर , बांद्रा पूर्व , मुंबई -५१, यांच्या कार्यालयामार्फत खालील दर्शविलेल्या कामाकरिता दर निश्चित करण्यासाठी अशा प्रकारच्या काम असलेल्या ठेकेदार / एजन्सीकडून / कंपनी कडून कोटेशन मागविण्यात येत आहे. खाली दिलेल्या कामाचे आयटम चे कोटेशन वर शिक्क्यानिशी मोहरबंद पाकीट ८ दिवसांच्या आत उपरोक्त कार्यालयात पोहचतील असे पाठवावे .

कामाचे नाव:-महावीर नगर, कांदिवली, येथील सीटीएस नं १२८ अ-१/२ (पार्ट) मुंबई या ठिकाणी ३००मेट्रिक घन क्षमतेचा मेडिया बायो रिऍक्टर, अर्धस्वयंचलित प्रकारचा मलनिःस्सारण प्रकल्पचे रचना ,प्रवठा , उभारणी , चाचणी , कमिशनिंग तसेच आवश्यक असलेल्या सर्व नाहरकत प्रमाणपत्रासहित प्रकल्प उभारणे .तसेच कॉरस बार स्क्रीन ,उपयुक्त एअरग्रीड इक्वीलायझेशन टाकीसाठी फीडपंप , एअरग्रीड , अरेशन टाकीसाठी स्टेनर, एअर ब्लोवर , ट्यूब सेटलिंग टाकीसाठी माध्यम , स्लजपंप , ओझोनेटर ओझोनेशन पंप , क्रिया केलेल्या पाण्याच्या टाकीसाठी एअरग्रीड फिल्टर फीडपंप ,प्रेशर सॅण्ड फिल्टर , सक्रिय कार्बन फिल्टर, कार्टिज फिल्टर, फिल्टर प्रेस, फिल्टर प्रेस फीड पंप, जोडलेल्या नळ्याचे वाल्व आणि फिटिंग्ज , मोटर, इलेक्ट्रिकल पॅनल ,उपकरणांची अर्थिंग , लेवल स्विच बसविणे तसेच तीन वर्षांची विनामुल्य दुरुस्ती कालावधी प्रकल्प चालविणे व व्यापक देखभाल करणे.

कामाचे आयटम:- महावीर नगर, कांदिवली, येथील सीटीएस नं १२८ अ-१/२ (पार्ट) मुंबई या ठिकाणी ७५०केजी प्रति दिवस क्षमतेचा सेंद्रिय घन कचरा कम्पोस्टर प्रकल्पाचे रचना ,प्रवठा, उभारणी , चाचणी , कमिशनिंग तसेच आवश्यक असलेल्या सर्व नाहरकत प्रमाणपत्रासहित प्रकल्प उभारणे .तसेच श्रेडर असेम्बली, कंपोस्टर ड्रम, MS-FRP आधारीत स्ट्क्चर, कंपोस्ट ट्रे, विद्युत मिटर व अन्य कंट्रोल पॅनल बसविण्यासाठी पावडर कोटेट कॅबिनेट आणि फिटिंग्ज , मोटर, इलेक्ट्रिकल पॅनल उपकरणांची अर्थिंग करणे तसेच तीन वर्षांची विनामूल्य दुरुस्ती कालावधी प्रकल्प चालविणे व व्यापक देखभाल करणे.

## अटी व शर्ती :

- १) दरपत्रकावर कामाचे नाव लिहणे बंधनकारक आहे
- २) दरपत्रकातील दर हे अंकात व अक्षरात जी. एस टी व्यतिरिक्त व जी. एस टीसह स्वतंत्र लिहलेले असावे.
- ३) दरपत्रकावर ठेकेदार/एजन्सी/कंपनी प्रोप्रारायटर यांचे हस्ताक्षर व स्टॅम्प असणे बंधनकारक आहे.
- ४) ठेकेदार /एजन्सी / कंपनी यांनी पूर्ण भरलेले व सही शिक्का निशी योग्य त्या कागपत्रा सह मोहरबंद लिफाफ्यात कोटेशन सादर करावे .
- ५) दरपत्रक स्वीकारणे किंवा रद्द करणे याबाबत कार्यकारी अभियंता / विद्युत विभाग / मुंबई मंडळ याना पूर्ण अधिकार राहील .
- ६) सदरचे कोटेशन हे वरील आयटम चे दर निश्चित करण्यासाठी मागविण्यात आले आहेत
- ७) मलनिःस्सारण यंत्रणा व सेंद्रिय घन कचरा कम्पोस्टर यासाठी वेगवेगळी मोहरबंद लिफाफ्यात कोटेशन सादर करावे

कार्यकारीअभियंता विदुयत विभाग / मुंबई मंडळ